



NOTES

- EXISTING CURB, GUTTER AND SIDEWALK SHALL BE CUT AT THE FIRST SCORE LINE BEYOND THE NEW DRIVEWAY LOCATION WITH AN ABRASIVE TYPE SAW TO A MINIMUM DEPTH OF 1 1/2". THE OLD CURB, GUTTER AND SIDEWALK SHALL BE ENTIRELY REMOVED AND REPLACED WITH 4000 PSI (6 SACKS PER CY) CONCRETE AS SHOWN.
- 1/2" EXPANSION JOINT MATERIAL SHALL BE PLACED ALONG EACH SIDE OF ALL NEW DRIVEWAY APPROACHES. WHERE SIDEWALKS, CURBS AND GUTTERS ARE EXISTING COLD JOINTS OR SLIP DOWELS MAY BE SUBSTITUTED.
- A TRAVERSE WEAK PLANE JOINT SHALL BE INSTALLED ON THE CENTERLINE OF ALL DRIVEWAYS. THE LONGITUDINAL LINE, AS SHOWN, SHALL BE A WEAK PLANE JOINT 4' FROM BACK OF SIDEWALK. SCORE LINES SHALL BE PLACED ONLY IN THIS 4' SIDEWALK AREA.
- NEW DRIVEWAY APPROACHES SHALL NOT ENCROACH WITHIN 10' OF CURB RETURNS. MINIMUM LENGTH OF FULL HEIGHT CURB BETWEEN COMMERCIAL APPROACHES SHALL BE 20 FEET.
- ABANDONED DRIVEWAY APPROACHES SHALL BE REMOVED AND REPLACED WITH STANDARD CURB AND GUTTER.
- WHERE EXISTING FACILITIES ARE NON-CONFORMING, APPROACHES MAY BE MODIFIED AS DIRECTED BY THE CITY ENGINEER.
- INSTALL 1/2" EXPANSION JOINT WHEN CONCRETE IS TO BE INSTALLED BEHIND DRIVEWAY APPROACH.
- RAMP LENGTH CAN VARY (1.5' MINIMUM) AS REQUIRED TO SATISFY A.D.A. REQUIREMENTS FOR CURB ADJACENT SIDEWALK UPON APPROVAL BY THE CITY ENGINEER.
- ALL CONCRETE SHALL BE 4000 PSI (6 SACKS PER CUBIC YARD), 3/4" AGGREGATE.

CITY OF NAPA

PUBLIC WORKS DEPARTMENT

STANDARD DRIVEWAY
APPROACH - SHORT RAMP

DRAWN BY: LFM
DATE: 08/2018
SCALE: NONE
FIELD NOTES:

CHECKED BY: JGF
APPROVED BY: JRL
DRAWING NO. S-5A