



NOTES

1. CONCRETE MUST BE TACK COATED PRIOR TO AC PLACEMENT.
2. YOU MUST ARRANGE FOR CITY INSPECTION BEFORE PCC IS PLACED, BACKFILL MUST BE COMPACTED BEFORE CITY INSPECTION.
3. YOU MUST FURNISH, INSTALL AND MAINTAIN A STEEL PLATE OVER EACH CONCRETE COLLAR PLACED AROUND EACH FRAME OR BOX UNTIL THE ASPHALT CONCRETE IS PLACED TO FINISH GRADE.
4. ENCASEMENTS MUST BE SET 1/4" BELOW STREET SURFACE.
5. CONCRETE MUST BE SEVEN (7) SACK, 5000PSI, SHAMROCK MIX #9170GG, OR EQUAL.
6. A CIRCULAR HOLE MUST BE CUT AROUND THE APPURTENANCE USING A METHOD THAT PROVIDES A SMOOTH EDGE, AS APPROVED BY THE ENGINEER

CITY OF NAPA

PUBLIC WORKS DEPARTMENT

**WATER VALVE AND MONUMENT
ADJUSTMENT**

DRAWN BY:	BRL	CHECKED BY:	JGF
DATE:	06/2018	APPROVED BY:	JRL
SCALE:	NONE	DRAWING NO.	S-14A
FIELD NOTES:			