



NOTES

1. REFER TO CITY STD D-14 FOR STORM DRAIN MANHOLE AND CITY STD W-9 FOR WATER MANHOLE SETTING SPECIFICATIONS.
2. THE FINISH GRADE OF THE COVERS SHALL BE FLUSH WITH THE ADJACENT SURFACING.
3. PORTLAND CEMENT CONCRETE (P.C.C.) SHALL BE 5000 PSI (7 SACKS PER CUBIC YARD & 3/4\" AGGREGATE).
4. THE COVER SHALL BE MARKED WITH THE NAME OF THE ITEM IT IS SET OVER.
5. ALL STRUCTURES SHALL BE SET TO GRADE AFTER PAVING.
6. ROUND HOLES SHALL BE SAWCUT.

CITY OF NAPA

PUBLIC WORKS DEPARTMENT

TYPICAL METHOD FOR SETTING
STRUCTURES

DRAWN BY: BRL

CHECKED BY: JGF

DATE: 06/2018

APPROVED BY: JRL

SCALE: NONE

DRAWING NO.

FIELD NOTES:

S-14