



NOTES

1. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
2. TREE STAKE TO BE LOCATED ON PREVAILING WIND SIDE WHEN TREE IS IN LEAF.
3. INSTALL TREE'S ROOTBALL 2" ABOVE FINISHED GRADE.

CITY OF NAPA

PUBLIC WORKS DEPARTMENT

STREET TREE PLANTING
 SPECIFICATIONS FOR 15
 GAL TREES SINGLE METAL STAKE

DRAWN BY:	BRL
DATE:	06/2018
SCALE:	NONE
FIELD NOTES:	

CHECKED BY:	DMP
APPROVED BY:	JRL
DRAWING NO.	T-3