



NOTES

1. WELDED WIRE MESH SHALL BE #6 T304 STAINLESS STEEL WIRE MESH AND SHALL BE INSTALLED UNDER VALVE BOX AND WASHED GRAVEL.
2. INSTALL ASSEMBLY WITHIN VALVE BOX TO MAKE COMPONENTS ACCESSIBLE FOR SERVICE AND MAINTENANCE (TYPICAL).
3. SET TOP OF VALVE BOX FLUSH WITH FINISH GRADE.

CITY OF NAPA

PARKS & RECREATION SERVICES DEPARTMENT

REMOTE CONTROL VALVE

DRAWN BY:	BRL	CHECKED BY:	DMP
APPROVAL DATE:	06/2018	APPROVED BY:	JRL
SCALE:	NONE	DRAWING NO.	PL-2
REVISED DATE:			