



- 1 STRONGBOX STAINLESS STEEL NEMA 3R RAINPROOF ENCLOSURE (UL LISTED).
- 2 CONTROLLER ASSEMBLY. ASSEMBLED IN ENCLOSURE BY SITEONE GREEN TECH.
- 3 TERMINAL STRIP FOR VALVE WIRES.
- 4 POWER SWITCH / GFCI RECEPTACLE.
- 5 ELECTRICAL FLEX CONDUIT FOR POWER.
- 6 6" MIN THICK, CONCRETE PAD WITH ANCHOR BOLTS PER MANUFACTURER RECOMMENDATION. 6 SACK PCC.
- 7 FINISHED GRADE.
- 8 FLOW SENSOR TERMINAL BOARD.
- 9 1" CONDUIT AND SWEEP ELL WITH FLOW SENSOR CABLE.
- 10 3" CONDUIT AND SWEEP ELL FOR LEAD WIRES.
- 11 1" CONDUIT AND SWEEP ELL FOR MASTER VALVE WIRES.
- 12 1" CONDUIT AND SWEEP ELL FOR 110 VAC POWER LINE.
- 13 1" CONDUIT AND SWEEP ELL FOR GROUND WIRE.
- 14 10" ROUND VALVE BOX AROUND GROUND ROD. FILL WITH 3/4" CRUSHED ROCK.
- 15 5/8" X 8' GROUND ROD WITH #6 GROUND WIRE AND CLAMP. LOCATE 8'-12' FROM ENCLOSURE.
- 16 #6 GROUND WIRE SECURED TO BACKBOARD GROUNDING TERMINAL.

CITY OF NAPA

PARKS & RECREATION SERVICES DEPARTMENT

CENTRAL CONTROL ASSEMBLY

DRAWN BY:	BRL	CHECKED BY:	DMP
APPROVAL DATE:	06/2018	APPROVED BY:	JRL
SCALE:	NONE	DRAWING NO.	PL-3
REVISED DATE:			