



NOTES

1. SURVEYOR OR ENGINEER SETTING THE MONUMENT SHALL INDICATE EXACT POINT BY MAKING A CROSS ON THE CAP. SURVEYOR SHALL STAMP YEAR SET AND THEIR LICENSE TYPE & NUMBER.
2. THE DEPTH OF THE MONUMENT POST SHALL BE LENGTHENED OR SHORTENED AS DICTATED BY THE GROUND CONDITIONS OR AS DIRECTED BY THE CITY ENGINEER. IN SOFT GROUND OR FILL AREAS THE MONUMENT POST SHALL BE LENGTHENED TO BED IT ON A STABLE BASE. IN ROCK IT SHALL BE KEYED OR DOWELED PERMANENTLY TO THE ROCK AS DIRECTED BY THE CITY ENGINEER.
3. WHEN THE MONUMENT IS TO BE INSTALLED IN AN EXISTING STREET WHERE THE CROWN IS NOT AT STANDARD ELEVATION, THE TOP OF THE MONUMENT SHOULD BE SET 8" BELOW THE FUTURE STREET SURFACE OR AS DIRECTED BY THE CITY ENGINEER. IT MAY BE NECESSARY TO USE A RISER PIPE.

CITY OF NAPA

PUBLIC WORKS DEPARTMENT

STANDARD PERMANENT MONUMENT

DRAWN BY:	LFM
APPROVAL DATE:	06/2018
SCALE:	NONE
REVISED DATE:	08/2021

CHECKED BY:	IHH
APPROVED BY:	JBL
DRAWING NO.	

S-13