



REQUIRED CLEARANCES FOR ROLL-OFF VEHICLE	
DESCRIPTION	DIMENSION
VERTICAL (APPROACH & EXIT)	14-FEET HIGH
VERTICAL (RAILS RAISED)	25-FEET HIGH
LATERAL	10-FEET LONG
SERVICE AREA LENGTH (DIRECT APPROACH)	75-FEET LONG

ROLL-OFF CONTAINERS

REQUIRED CLEARANCES FOR COMPACTORS	
DESCRIPTION	DIMENSION
VERTICAL (APPROACH & EXIT)	14-FEET HIGH
VERTICAL (RAILS RAISED)	25-FEET HIGH
SERVICE AREA LENGTH (DIRECT APPROACH)	75-FEET LONG
LATERAL	2-FEET AROUND COMPACTOR

COMPACTORS

NOTES

1. A MINIMUM OF 50 FEET IS REQUIRED FOR ACCESS TO TRASH ENCLOSURE BINS. A MINIMUM OF 75 FEET IS REQUIRED FOR ACCESS TO COMPACTORS AND ROLL-OFF CONTAINERS.
2. ROLL-OFF BOX COLLECTION LOCATED AT A LOADING DOCK MUST HAVE BUMPER PADS INSTALLED TO AVOID UNDUE DOCK DAMAGE FROM THE HEAVY CONTAINER.
3. ROLL-OFF CONTAINERS SHALL BE PLACED ON A LEVEL SURFACE.
4. CONTACT THE CITY'S AUTHORIZED CONTRACTOR AT (707) 255-5200 FOR AN ON SITE PLACEMENT INSPECTION AND BEFORE INSTALLING ANY LOADING DOCK BUMPER RAILS.
5. ALL COMPACTORS MUST HAVE 28 INCHES INSIDE RAIL DIMENSIONS AND 34 INCHES EXTERIOR RAIL DIMENSIONS.
6. COMPACTORS MAY REQUIRE AN ELECTRICAL OUTLET.
7. COMPACTORS MUST BE LEAK PROOF TO PREVENT DISCHARGE INTO THE CITY'S STORM DRAIN SYSTEM.
8. CONTACT THE CITY'S AUTHORIZED CONTRACTOR AT (707) 255-5200 PRIOR TO PURCHASING, RENTING, OR INSTALLING A COMPACTOR TO ENSURE SERVICING COMPATIBILITY WITH HAULING VEHICLES.
9. COMPACTORS PLACED INSIDE A BUILDING SHALL PROVIDE MINIMUM CLEARANCES AS OUTLINED ABOVE.

CITY OF NAPA

UTILITIES DEPARTMENT

TITLE
**COLLECTION CLEARANCES
 (ROLL-OFF BINS & COMPACTOR)**

DRAWN BY: DEH	CHECKED BY: SL
APPROVAL DATE: 01/06/22	APPROVED BY: KM
SCALE: NONE	DRAWING NO. SWR-4
REVISED DATE: 09/2021	